


Experimental Testing of a 1MW sCO₂ Turbocompressor



Logan Rapp
Sandia National Laboratories
3rd European sCO₂ Conference
September 20, 2019

David Stapp
Peregrine Turbine Technologies

SAND2019-10928 C




Sandia National Laboratories is a multimission laboratory managed and operated by National Technology & Engineering Solutions of Sandia, LLC, a wholly owned subsidiary of Honeywell International Inc., for the U.S. Department of Energy's National Nuclear Security Administration under contract DE-NA0003525.



Brayton Laboratory



Heat Exchanger Testing



Pressure Fatigue Testing



Turbomachinery Testing



Bearings Testing



Seals Testing

Recompression Closed Brayton Cycle (RCBC) configuration



Commissioned in 2012

Only experimental sCO₂ RCBC ever to have been operated

Many papers and conference proceedings have been published on the data from the RCBC experiments






780 kW electric immersion heat


2.3 MW duty High Temp
Recuperator

1.6 MW duty Low Temp
Recuperator

540 kW water/sCO₂ cooler

Hydro-Pac Piston compressor
pump





Peregrine Turbine Technologies Turbocompressor





Design Conditions:

- 118,000 RPM
- 750 C Turbine Inlet (1382 F)
- 42.9 MPa compressor discharge (6222 psi)

Loop Maximum Conditions:

- 538 C Turbine Inlet (1000 F)
- 17.2 MPa compressor discharge (2500 psi)



7 | Blowdown Start Method



Loop is preconditioned using Hydropac


- Compressor inlet above supercritical conditions
- Turbine inlet at approximately target for test

Valve Positions


- BV7 is closed
- BV8 and SV are opened

Once P500A -P501 > dP_min:


- BV7 is opened and BV8 and SV are closed



8 Blowdown start plots



Blowdown Pressure=1670 psi



Blowdown Pressure=1400 psi

Summary of tests to date




Test Number	Test Date	Test Duration	TIT (°F)	Compressor Discharge Pressure (psi)	Max PR
1	8/9/2018	00:00:32	225	1240	1.2
2	10/10/2018	00:18:40	420	1400	1.25
3	11/14/2018	00:20:46	645	1750	1.59
4	3/1/2019	00:03:32	610	1460	1.26
5	3/6/2019	00:08:23	530	1510	1.3
6	4/4/2019	00:03:18	530	1510	1.28
7	5/7/2019	8:05:44	570	1475	1.27

Bearing Issues



In Tests #1-3, both the thrust bearing and the radial bearings experienced rubs/failures


Spikes in pressure indicate thrust bearing rubs





Secondary Flows



Valve F regulates venting pressure on aft side of thrust disk rotor – acts as balance piston



Thrust bearing issue resolved





By adjusting Valve F and the TCV the force on the rotor was balanced.

Radial Bearing Issues




In all tests (except #7 – 8 hr test), the turbine end radial bearing failed

Possible causes of failure:

- Blowdown start
 - Reduce blowdown pressure
- Critical speed causing rotor instability
 - Physical evidence of bearing failure shows yielded foils at a specific clocking; not indication of rotor instability
- Radial load caused by non-uniform turbine inlet conditions
 - Resolved with instrumentation



Turbine Inlets




Leg "A" was consistently lower temperature than the other 3

Original and New Turbine Inlet RTD insertions



Original




A

B


C

D

New



Turbine Inlet Temp with new Insertion depth





No difference in centerline temperature of turbine inlets

Increased L/D of aft radial bearing



The aft radial bearing length/diameter ratio was increased to increase load capacity and the damping of the bearing

Start Number	Turbine Inlet Temp (F)	Blowdown Pressure (psi)	Outcome
1	460	1330	Unsuccessful
2	500	1360	Unsuccessful
3	525	1425	Unsuccessful
4	550	1450	Successful



Next Steps



Test turbocompressor up to limits of current loop (1000F @ 2500 psi)

Run sensitivity tests of turbocompressor performance with compressor inlet temperature

Map performance of turbocompressor over variety of off-design conditions

Work with Peregrine Turbine Technologies to test turbocompressor up to full design conditions



Thank you